

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT

1. CONTRACT ID CODE _____ PAGE _____ OF _____ PAGES

2. AMENDMENT/MODIFICATION NO. _____		3. EFFECTIVE DATE _____	4. REQUISITION/PURCHASE REQ. NO. _____	5. PROJECT NO. <i>(If applicable)</i> _____
6. ISSUED BY _____ CODE _____		7. ADMINISTERED BY <i>(If other than Item 6)</i> _____ CODE _____		

8. NAME AND ADDRESS OF CONTRACTOR <i>(No., street, county, State and ZIP Code)</i> CODE _____ FACILITY CODE _____	(X)	9A. AMENDMENT OF SOLICIATION NO. _____
		9B. DATED <i>(SEE ITEM 11)</i> _____
		10A. MODIFICATION OF CONTRACT/ORDER NO. _____
		10B. DATED <i>(SEE ITEM 11)</i> _____

11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS

The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers is extended, is not extended. Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods:
 (a) By completing items 8 and 15, and returning _____ copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment your desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. ACCOUNTING AND APPROPRIATION DATA *(If required)* _____

13. THIS ITEM ONLY APPLIES TO MODIFICATION OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.

CHECK ONE	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: <i>(Specify authority)</i> THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES <i>(such as changes in paying office, appropriation date, etc.)</i> SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b).
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER <i>(Specify type of modification and authority)</i>

E. IMPORTANT: Contractor is not, is required to sign this document and return _____ copies to the issuing office.

14. DESCRIPTION OF AMENDMENT/MODIFICATION *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER <i>(Type or print)</i>		16A. NAME AND TITLE OF CONTRACTING OFFICER <i>(Type or print)</i>	
15B. CONTRACTOR/OFFEROR	15C. DATE SIGNED	16B. UNITED STATES OF AMERICA	16C. DATE SIGNED
<i>(Signature of person authorized to sign)</i>		<i>(Signature of Contracting Officer)</i>	

Item 14. Continued.

CHANGES TO THE BID SCHEDULE.

1) Replace the Bidding Schedule with the attached new Bidding Schedule, bearing the notation "ACCOMPANYING AMENDMENT NO. 0001 TO SOLICITATION NO. DACW63-01-B-0009."

CHANGES TO THE SPECIFICATIONS.

2) Replacement Sections - Replace the following section with the accompanying new section of the same number and title, bearing the notation "ACCOMPANYING AMENDMENT NO. 0001 TO SOLICITATION NO. DACW63-01-B-0009."

SECTION 02220 DEMOLITION

CHANGES TO THE DRAWINGS.

3) Replacement Drawings.- Replace the drawings listed below with the attached new drawings of the same number, bearing the notation "AM #0001":

seq3.cal Seq 3 SLAB PLAN AND SECTIONS

END OF AMENDMENT

Solicitation No. DACW63-01-B-0009

Concrete Abutment Repair (Title)
Town Bluff Project Office, Woodville, TX (Location)

BIDDING SCHEDULE
 (To be attached to SF 1442)

Item No.	Description	Estimated Quantity	Unit	Unit Price	Amount
0001	Site Preparation (Concrete demolition, removal and disposal)	Job Sum	LS	***	\$_____
0002	Derrick Stone (Remove, Store, and Replace)	20	EA	\$_____	\$_____
0003	Vertical Joint Protection, A. W12X53 Piling B. C7X9.8 Channel	100 100	FT FT	\$_____ \$_____	\$_____ \$_____
0004	Compacted Fill A. Impervious B. Non-Expansive	450 500	CY CY	\$_____ \$_____	\$_____ \$_____
0005	Retrofit Waterstop	130	LF	\$_____	\$_____
0006 (Am#1)	Apron Concrete	155	CY	\$_____	\$_____
0007 (Am#1)	L-Wall Concrete	15	CY	\$_____	\$_____
0008	New Drain Pipe	130	LF	\$_____	\$_____
Total Bid				\$_____	

BIDDING SCHEDULE (cont)

NOTES:

1. ARITHMETIC DISCREPANCIES (EFARS 14.407-2)

(a) For the purpose of initial evaluation of bids, the following will be utilized in resolving arithmetic discrepancies found on the face of the bidding schedule as submitted by bidders:

- (1) Obviously misplaced decimal points will be corrected;
- (2) In case of discrepancy between unit price and extended price, the unit price will govern;
- (3) Apparent errors in extension of unit prices will be corrected; and
- (4) Apparent errors in addition of lump-sum and extended prices will be corrected.

(b) For the purposes of bid evaluation, the Government will proceed on the assumption that the bidder intends his bid to be evaluated on the basis of the unit prices, extensions, and totals arrived at by resolution of arithmetic discrepancies as provided above and the bid will be so reflected on the abstract of bids.

(c) These correction procedures shall not be used to resolve any ambiguity concerning which bid is low.

2. If a modification to a bid based on unit prices is submitted, which provides for a lump sum adjustment to the total estimated cost, the application of the lump sum adjustment to each unit price in the bid schedule must be stated. If it is not stated, the bidder agrees that the lump sum adjustment shall be applied on a pro rata basis to every unit price in the bid schedule.

3. Bidders must bid on all items.

4. Costs attributable to Division 01 - General Requirements are assumed to be prorated among bid items listed.

5. For the purpose of this solicitation, the word "item" shall be considered to mean "schedule" as used in Provision 52.214-0019, CONTRACT AWARD--SEALED BIDDING--CONSTRUCTION, in Section 00100 INSTRUCTIONS, CONDITIONS, AND NOTICES TO BIDDERS, excluding additives, deductives, or optional items.

Solicitation No. DACW63-01-B-0009

BIDDING SCHEDULE (cont)

NOTES:

6. ABBREVIATIONS

For the purpose of this solicitation, the units of measure are represented as follows:

- a. EA (each)
- b. FT (feet)
- c. CY (cubic yards)
- d. LF (linear feet)
- e. LS (lump sum)

END OF BIDDING SCHEDULE

SECTION 02220

DEMOLITION
12/97
Amendment 0001

PART 1 GENERAL

1.1 REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to in the text by basic designation only.

ENGINEERING MANUALS (EM)

EM 385-1-1 (1996) U.S. Army Corps of Engineers Safety and Health Requirements Manual

1.2 GENERAL REQUIREMENTS

The work includes demolition of identified items and materials, and removal of resulting rubbish and debris. Rubbish and debris shall be removed from Government property daily, unless otherwise directed, to avoid accumulation at the demolition site. Materials that cannot be removed daily shall be stored in areas specified by the Contracting Officer. In the interest of occupational safety and health, the work shall be performed in accordance with EM 385-1-1, Section 23, Demolition, and other applicable Sections.

1.3 MEASUREMENT

Preparing the construction area will not be measured as a separate pay items.

1.4 PAYMENT FOR SITE PREPARATION

All costs associated with preparing the construction area, demolition, removal, and disposal of the concrete apron will be subsidiary to the contract job sum price for "Site Preparation (Concrete demolition, removal and disposal)". This price shall constitute full compensation for all labor, equipment, tools, and incidentals necessary prepare the construction area including the demolition, removal, and disposal of the concrete apron.

1.5 DERRICK STONE

1.5.1 Measurement

Measurement for derrick stone removal, storing, and replacing will be by each derrick stone that is removed, stored, and replaced.

1.5.2 Payment

Payment for removal, storing, and replacing derrick stones will be by the contract bid price for "Derrick Stone (Remove, Store, and Replace)". This price shall constitute full compensation for all labor, equipment, tools, cranes, and incidentals necessary to accomplish the work. Any derrick

stones that are damaged as a result of the contractor's action or failure to act appropriately shall be replaced by the contractor at no additional cost to the Government.

1.6 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01330 SUBMITTAL PROCEDURES:

SD-03 Product Data

Work Plan; G,

The procedures proposed for the accomplishment of the work. The procedures shall provide for safe conduct of the work, including procedures and methods to provide necessary supports, lateral bracing and shoring when required, careful removal and disposition of materials specified to be salvaged, protection of property which is to remain undisturbed, coordination with other work in progress, and timely disconnection of utility services. The procedures shall include a detailed description of the methods and equipment to be used for each operation, and the sequence of operations in accordance with EM 385-1-1.

1.7 PROTECTION

1.7.1 Protection of Existing Property

Before beginning any demolition work, the Contractor shall survey the site and examine the drawings and specifications to determine the extent of the work. The Contractor shall take necessary precautions to avoid damage to existing items to remain in place; any damaged items shall be repaired or replaced as approved by the Contracting Officer. The Contractor shall coordinate the work of this section with all other work .

1.7.2 Environmental Protection

The work shall comply with the requirements of Section 01410 ENVIRONMENT PROTECTION .

PART 2 PRODUCTS (Not Applicable)

PART 3 EXECUTION

3.1 EXISTING STRUCTURES

Portions of existing structures indicated shall be removed as shown on the contract drawings.

Approximately 45 cubic yards of sand/cement grout were pumped under the concrete apron slab during 1992. The contractor shall remove any grout deposits or large rocks that may be found under the concrete apron during demolition of the concrete apron or excavation for the new drain pipe installation. (Am#1)

3.1.1 Removal of Concrete Apron

Existing concrete apron shall be removed in the areas shown on the drawings. Concrete shall be removed in such a manner that no damage will occur in adjacent slabs. All concrete apron to be removed where the limits of removal are not at existing joints, shall be scored to a depth shown on the drawings, with a concrete saw or other similar equipment. Scoring shall be done in a straight line and shall be parallel to the existing joints where possible. Care shall be taken not to damage adjacent slabs. If adjacent slabs are damaged during removal operations, as determined by the Contracting Officer, the damaged portion shall be removed and replaced at the Contractor's expense and in a manner as directed by the Contracting Officer. If cracks or overbreakage into adjacent concrete slabs occur during removal operations, the area within the scoring line shall be widened sufficiently to remove cracks or overbreakage, but if cracks or overbreakage fall within one foot of the next adjacent joint, the remainder of the slab adjacent to that joint shall be removed. During removal operations and after concrete has been removed, the Contractor shall exercise all precautions necessary to keep water from entering the subgrade. If water should enter the excavation, the Contractor shall remove the water by pumping and shall allow adequate time for the subgrade to dry, as determined by the Contracting Officer. Any slab or portion of slabs damaged due to negligence on the part of the Contractor shall be removed and replaced at his own expense. Concrete which is removed shall be disposed of in the designated waste areas.

3.2 DISPOSITION OF MATERIAL

Title to material and equipment to be demolished, is vested in the Contractor upon receipt of notice to proceed. The Government will not be responsible for the condition, loss or damage to such property after notice to proceed.

3.2.1 Unsalvageable Material

Concrete, masonry, and other noncombustible material, except concrete permitted to remain in place, shall be disposed of in the disposal area located as stated on the drawings. The fill in the disposal area shall be placed as directed by the Contracting Officer's Representative and after disposal is completed, the disposal area shall be uniformly graded to drain. Combustible material shall be disposed of off the site.

3.3 CLEAN UP

Debris and rubbish shall be removed from excavations. Debris shall be removed and transported in a manner that prevents spillage on streets or adjacent areas. Local regulations regarding hauling and disposal shall apply.

-- End of Section --